

**Annexure -I**

NAME OF THE WORK:- REPAIRING AND RENOVATION OF TOILET BLOCK AND COMMERCIAL COMPLEX, DAILY MARKET IN WARD NO.- 9, NORTH LAKHIMPUR, ASSAM.

Sl No.	Particulars	Unit	Quantity	Dept Rate(Rs)	Quoted rate(Rs)	Amount(Rs)
1	Providing vitreous China wash basin with CI/MS brackets, C.P brass chain with plug,PVC waste pipe including painting of fittings and brackets, cutting and making good the walls wherever required. (Pillar cock, stop cocks, waste coupling are to be paid separately)	nos	3	2985.35		
2	Providing, fitting and fixing 24mm/ 29mm thick polymer reinforced moulded PVC door shutters fixed to the chowkath with necessary hinges, screws, bolts etc. as specified and directed at all levels (Door fixtures and fittings to be measured and paid seperately)	nos	4	1617.40		
3	Providing fitting and fixing vitreous china squatting plate urinal with automatic flushing cistern with standard flush pipe and CP brass spreader andbrass unions, etc. complete including painting of fittings and brackets, cutting and making good the walls & floors wherever required.	nos	3	3377.65		
4	Providing fitting and fixing vitreous water closet squatting pan (Indian type W.C Orissa pattern) with all fittings and fixtures complete including cutting and making good to the walls and floors wherever required. (Flushing Cistern to be paid separately)	nos	3	2945.72		
5	112 mm thick reinforced brick wall in prop 1:5 reinforced with two lines of M.S rod/ Tor steel as specified embeded in 38 mm thick concrete course in prop.1:2:4 with coarse agg. 12mm down at every fourth courses embeded with protruding rod in column including curing etc.complete as directed ( M.S rod/Tor steel shall be measured and paid separately) in super structure above plinth up to 1st floor level.	sqm	16.47	698.72		
6	15 mm thick Cement plaster in single coat on single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed.	sqm	32.94	157.54		
7	<b><i>Providing corrugated galvenised Iron sheet roofing of TATA SHAKTEE / SAIL including fitting and fixing necessary galvenised J or L hooks, bolts and nuts 8 mm dia with bitumen washer 25 mm dia x 3 mm thick and 1.6 mm thick limpet washer complete excluding cost of roof truss, purlin etc. (Roof trusses and purlin etc.to be measured and paid senarately).</i></b>	sqm	297.3	481.98		

8	Providing fitting, hoisting and fixing of roof trusses including purlins fabricated using MS circular hollow section conforming to relevant I.S. code, as per approved design and drawings including providing M.S. cleats, base plates, bolts and nuts and one coat of red oxide Zinc Chromate primer and two coats of approved enamel paints complete including fitting necessary cleats etc. for fixing ceiling joists as per design and drawing as directed.	qtl	6.53	9457.73		
9	<b>65 mm thick cement concrete floor consisting of 50 mm under layer of cement concrete in prop. 1:3:6 (1cement : 3 coarse sand : 6 coarse aggregate of 25mm and down) and 15 mm thick wearing layer in cement concrete in prop. 1:1:2 (1cement :1 coarse sand : 2 coarse aggregate of size 10mm down) laid in panels and finished with a floating coat of neat cement finish (using cement slurry for bond @ 2.75 kg. per square metre of floor area) including curing etc. complete as directed.</b>	sqm	16.05	546.88		
10	<b>Supplying fitting, fixing, testing and commissioning of following capacity motor(Crompton Greaves/Auatic/Aquatic/CRIV Guardmake complete with necessary connection as approved specific and directed by the department 0.5 HP singl phase 1420 rpm</b>	nos	1	7591.65		
11	Supplying, fitting and fixing suction pipes plain/bevel ended, conforming to relevant IS codes of practice including supplying and fitting of accessories, lowering of assembly pipes concentrically in the casing pipes complete as directed.	rm	8	474.01		
12	Labour for boring hole for inserting tube well pipes through different soil/ rock media including hire charges of drill pipes, scaffolding, tools and plants as necessary and taking out the same and lowering pipes, fittings complete as directed by the Department.	rm	8	462.74		
13	Supplying fitting and fixing Pipes with all necessary fittings in exposed or in trenches including trenching and refilling the same etc complete as directed 75mm dia	rm	8	928.35		
14	Supplying fitting and fixing Pipes with all necessary fittings in exposed or in trenches including trenching and refilling the same etc complete as directed B) uPVC pipe with uPVC fittings ( Using uPVC high pressure pipe) (Using SUPREME/ PRINCE/ SFMC/ FUSION brand pipe)	rm	12.2	820.85		
15	25mm dia	rm	15	132.05		
16	Supplying fitting and fixing C.P. bib cock 15mm dia of approved brand as directed and specified. (G.I. & C.P pipes will be measured separately)	cum	6	778.83		

17	Providing and laying plain/reinforced cement concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing complete but excluding cost of form work and reinforcement for reinforced cement concrete work (form work and reinforcement will be measured and paid separately)	sqm	0.8375	6488.11		
18	Providing form work of ordinary timber planking so as to give a rough finish including centering, shuttering, strutting and propping etc., height of propping and centering below supporting floor to ceiling not exceeding 4.0M and removal of the same for in-situ reinforced concrete and plain concrete work in	sqm	13.4	269.90		
19	Structural steel work in sigle sections including cutting, hoisting, fixing in position and applying a priming coat of red lead paint (up to 4.6m height) from plinth level including drilling holes, supplying, fitting and fixing with bolts and nuts or welding, if necessary as directed.	qtl	2.67	7432.22		
	Total=					

Executive Officer  
North Lakhimpur Municipal Board